

HOTEL NETWORK

You are required to design and implement a Modern Hotel Network. The hotel has three floors; in the first floor there are three departments (Reception, Store and Logistics), in the second floor there are three departments (Finance, HR and Sales/Marketing), while the third floor hosts the IT and Admin. Therefore, the following are part of the considerations during the design and implementation.

- 1) There should be three routers connecting each floor (all placed in the server room in IT Department)
- 2) All routers should be connected to each other using serial DCE cable
- 3) The network between the routers should be 10.10.10.0/30, 10.10.10.4/30, 10.10.10.8/30
- 4) each floor is expected to have one switch (Placed in respective Floor)
- 5) Each floor is expected to have WiFi networks connected to laptop and phone.
- 6) Each department is expected to have a printer
- 7) Each department is expected to be in different VLAN with the following details.
 - 1st Floor
 - ➔ Reception : VLAN 80 Network 192.168.8.0/24
 - ➔ Store : VLAN 70 Network 192.168.7.0/24
 - ➔ Logistics : VLAN 60 Network 192.168.6.0/24
 - 2nd Floor
 - ➔ Finance : VLAN 50 Network 192.168.5.0/24
 - ➔ HR : VLAN 40 Network 192.168.4.0/24
 - ➔ Sales : VLAN 30 Network 192.168.3.0/24
 - 3rd Floor
 - ➔ Admin : VLAN 20 Network 192.168.2.0/24
 - ➔ IT : VLAN 10 Network 192.168.1.0/24
- 8) Use OSPF as the routing protocol to advertise routes.
- 9) All Devices in the network are expected to obtain IP address dynamically with their respective router configured as the DHCP server.
- 10) All the devices in the network are expected to communicate with each other
- 11) Configure SSH in all the routers for remote login.
- 12) In IT department, add PC called Test-PC to port fa0/1 and use it to test remote login
- 13) Configure port security to IT department to allow only Test-PC to access port fa0/1 (use sticky method to obtain mac-address with violation mode of shutdown)